



PROGRESSIVE

SPORTS CONSTRUCTION GROUP 765-987-7999 866-637-5611 411 S. Pearl St. Spiceland IN 47385 USA www. progressivescg.com Form PSCG\_1310\_Sub15-R

	ARCHITECT:	
	CONTRACTOR:	
	SUPPLIER:	
Printed in U.S.A.	DATE: REVISED:	

1310

## Specifications—Progressive 1310

Wall Mounted Stationary Backstop (12"-144")

**Product Description** 

**EXTENSION:** Backstop shall be a wall mounted and wall braced style with the bank face being extended (12" to 144") from the supporting wall. Extension frame shall be constructed of (4) 2½" (6.35 cm) OD 13 gauge and 2½" (5.72 cm) OD 14 gauge steel tubes terminating with fabricated heavy steel plates for attachment to wood all pads and the backboard. Frame shall be adjustable for a plus or minus 6" (15.24 cm) variation from face of bank to wall.

**BRACING:** Frame shall be braced horizontally by use of  $\frac{1}{4}$ " x  $\frac{1}{4}$ " (6.35 mm x 3.17 cm) steel cross brace terminating in precision die formed clamps.

**SUPPORT:** Backstops with extensions greater than 3'-0" (91.44 cm) or with height adjusters will be supported in playing position by two ¼" (6.35 mm) welded link chains with turnbuckles for leveling.

**MOUNTING:** Backstop shall be provided with 2 x 8 (5.08 x 20.32 cm) southern yellow pine wall pads at attachment points. All edges shall be chamfered and finished with high-gloss polyurethane.

**FINISH:** All metal parts shall be finished with choice of gloss black or gloss white powder coat. Other colors optionally available.

**WARRANTY:** There is a 25-year limited warranty on all Progressive backstop structures and fittings.

**OPTIONS:** Backstop can be provided with any of several different styles of backboards goals and padding. Specify types desired.

**ACCESSORIES:** See separate sheets for Height Adjusters.

## **LEED® Submittal Information**

Credit	Measure	
MRc4 – Recycled Content	Post Consumer Average 26.90%	Post Industrial 0%
MRc5 – Regional Materials	Raw materials are commodity items from multiple sources so extraction point cannot be determined. Final Manufacturing/Assembly in Spiceland, IN 47385	